



ALAIN HIRSCH *Construction Corp.*

Project Safety

The safety of every individual on or around an Alain Hirsch Construction Project Site is of the utmost importance to our firm. At each project site we promote safety by:

- Educating workers on safety requirements
- Providing equipment training to our workers and subcontractor partners
- Posting appropriate signage throughout the jobsite to alert workers to potential safety hazards
- Requiring workers to follow our strict safety and loss prevention program
- Empower all of our employees and those working on our jobsites to speak up and take action to correct unsafe situations

We are so committed to the well being of those who come in contact with our work that our safety principles go above and beyond OSHA (Occupational Safety and Health Administration) standards.

We welcome visitors to view the progress of each and every project. It is essential that visitors adhere to our safety guidelines.

For guests who are visiting our jobsites, be sure you receive a clear safety orientation from a member of our team and the appropriate personal protective equipment (PPE) to wear. In the meantime, here are some essential safety guidelines we'd like you to follow so you can plan ahead for your visit:

- Stay with a designated AHCC employee at all times.
- Wear hard-soled shoes or boots (no open toe shoes, sandals or high-heeled shoes).
- Keep your hard hat on at all times and wear any additional personal protective equipment that was provided to you.
- Keep a safe distance from the perimeter of the building. Do not lean or rest against any handrail or guardrail systems.
- Watch where you walk! Be cautious of slick or wet surfaces and tripping hazards.
- Do not cross any barricades, yellow caution tape, or red danger tape.
- Be aware of overhead hazards, such as crane loads, scaffold systems, or people on ladders.
- Be aware of moving equipment, such as trucks, forklifts, and backhoes. Equipment operators may have difficulty seeing you.
- Do not try to climb ladders or scaffold systems without permission. Maintain a three-point contact while climbing ladders—one person at a time, please!
- We know your phone calls are important but, PLEASE, please pay attention to your surroundings and watch your step.



ALAIN HIRSCH *Construction Corp.*

These rules may seem strict, however we know that by working together to follow these guidelines everyone can stay safe, productive and leave with a better understanding of who we are and the exciting work that we do.

For Alain Hirsch Construction Corp. employees and subcontractors:

- All Employees and/or Subcontractors will wear clothing with employers name and/or logo.
- Hard hats worn when falling object hazard is present
- Safety glasses and/or goggles
- Protective eyewear use
- Face shield available for bulk liquid task and grinding
- Hand protection used/worn as required
- Hearing protection worn
- Foot protection – absolutely no open toed shoes
- No short pants or skirts.
- No radios or headphones

Be Aware of the following:

- Emergency evacuation map posted.
- Emergency phone numbers posted
- Emergency eyewash and/or shower units accessible
- First aid kit location
- First aid trained competent person available where required
- Fire extinguishers location

Electrical Safety:

- GFCI's used for all portable electrical hand tools
- Strain relief integrity for cords and plugs in tact
- Extension cords rated for hard or extra hard usage
- Certified or listed equipment is used per manufacturer
- Electrical cords inspected & have all prongs intact.
- Electrical panels are labeled appropriately
- Strain relief intact for all flexible cords & plug fittings
- Electrical panel knockouts are in place
- Portable generators are grounded per NEC requirements
- Light bulbs for illumination protected from breakage
- Electric power tools are double insulated or grounded
- General housekeeping is neat and orderly
- Flammable liquids are in OSHA/FM metal safety cans
- MSDS openly available to all employees



ALAIN HIRSCH *Construction Corp.*

Electrical Safety Continued:

- Flammable liquids storage containers labeled properly
- Concrete work? Silica dust training documented for all
- All hazardous containers labeled appropriately
- Impact style air tools have safety clips or retainers.
- Lockout/Tagout is being used for appropriate tasks
- Pneumatic power tools have hoses secured
- Hot work permits used for grinding, cutting, welding
- Compressed air used for cleaning limited to 30 psi
- Impact tools, hammers kept free of splinters/mushrooms
- Ladders are safe and inspected as appropriate
- Unsafe hand tools are prohibited
- Wire rope and/or web slings used for lifting must have no visible deterioration
- Hooks used for lifting have safety latch in place
- Stair rails are required at 30" change in elevation or 4 risers
- Stairs or ladder provided for access points greater than 19"
- Extension or straight ladders must extend 3' beyond landing
- Step ladders are only used in open position
- Scaffolding must have guardrails
- Fall Protection where appropriate
- All wall or floor openings covered